Central Environmental Laboratories
Module 2, Batchelar Agricultural Centre, Batchelar Road
Palmerston North,4472
PO Box 6054 Awapuni Palmerston North,4412
New Zealand

CENTRAL ENVIRONMENTAL LABORATORIES

Analytical Report

COA No: 26/06715-1

P: +64 6 351 4475
E: cenlab@cenlab.co.nz

Palmerston North City Council
32 The Square
Private Bag 11034
Palmerston North 4442

Compliance of samples tested are assessed according to 'Water Services (Drinking Water Standards for New Zealand) Regulations 2022'

Date received: 19/11/2026 **Sample date:** 19/11/2026 **Sample type:** Treated

Sample	Test	Result	Units	Comments	Uncertainty
26/06715-01	**Time received:** 08:00		**Sampled by:** Alby Shaw	**Sample time:** 06:58	
Order no.: PO 4061					
Turitea Water Treatment Plant TP00147	Fluoride	0.73	g/m³	Complies with MAV of 1.5	
26/06715-02	**Time received:** 08:00		**Sampled by:** Alby Shaw	**Sample time:** 07:28	
Order no.: PO 4064					
Papaioea Park Bore Station TP00148	Fluoride	0.74	g/m³	Complies with MAV of 1.5	
26/06715-03	**Time received:** 08:00		**Sampled by:** Mike Gunther	**Sample time:** 07:26	
Order no.: PO 4064					
Takaro Bore Station TP00149	Fluoride	0.79	g/m³	Complies with MAV of 1.5	
26/06715-04	**Sample time:** 00:00				
Order no.: PO 4064					
Roberts Line Bore Station TP00150	Notes *	Offline			
26/06715-05	**Time received:** 08:00		**Sampled by:** Josh Green	**Sample time:** 07:43	
Order no.: PO 4064					
Keith Street Bore Station TP02023	Fluoride	0.74	g/m³	Complies with MAV of 1.5	
26/06715-06	**Time received:** 08:00		**Sampled by:** Josh Green	**Sample time:** 07:25	
Order no.: PO 4075					
Ashhurst Bore Station TP00158	Fluoride	0.88	g/m³	Complies with MAV of 1.5	
26/06715-07	**Time received:** 08:00		**Sampled by:** Josh Green	**Sample time:** 07:10	
Order no.: PO 4064					

Sample	Test	Result	Units	Comments	Uncertainty
Bunnythorpe Bore Station TP01205	Fluoride	0.76	g/m³	Complies with MAV of 1.5	

26/06715-08 **Time received:** 08:00 **Sampled by:** Mike Gunther **Sample time:** 07:45

Order no.: PO 4064

Longburn Bore Station TP00384	Fluoride	0.54	g/m³	Complies with MAV of 1.5	

26/06715-09 **Time received:** 08:00 **Sampled by:** Josh Green **Sample time:** 07:03

Order no.: PO 4064

Railway Road Bore Station TP04022	Fluoride	0.84	g/m³	Complies with MAV of 1.5	

< is less than > is more than, g/m³ is equivalent to mg/L and ppm, MAV - Maximum Acceptable Value. GV - Aesthetic Value

Observations, Comments and Calculations are not Accredited. Calculations are available on request.

Notes: * Test is not accredited.

Test Code	Test	Methodology	Detection Limit
F.002CG	Fluoride	APHA 24th Ed. 4110 B	0.1 g/m³
Obs.016	Notes	Non-endorsed observation.	

Test analysis was initiated on 19/11/2026.



Report released by **Johan Bosch** **Date: 20 November 2026**

Principal Analyst

Key Technical Person:

Nishani Thennakoon

This Laboratory is accredited by International Accreditation New Zealand.
Tests and sampling procedures have been performed in accordance with the conditions of our accreditation.
Where not supplied, detection limits and uncertainties are available on request.
When samples are collected by the client or an agent of the client, results reported apply only to samples as received at the Laboratory.
This report shall not be reproduced except in full, without the written approval of this laboratory.